


- The Tri-County Agricultural Area is comprised of watersheds with a significant amount of agricultural land use, much of which is in close proximity to the St. Johns River.
- Approximately 31,000 acres is irrigated vegetable cropland; predominantly potato, cabbage and sod.





**Federal Point** 














A three-year (1991-93) diagnostic project quantified and qualified nutrient loading from 10 representative area farms and results indicated




1) N and P loading is primarily associated with storm events.




2) Nitrogen loading occurred mostly during the growing season, P loading had no seasonal trend.


# Tributaries associated with agricultural areas have high concentrations of total nitrogen.



## Tributaries associated with agricultural areas also have high concentrations of total phosphorus.




<sup>\*</sup>Significant dairy operations have ceased and TP concentrations are trending downward




### Freshwater Reach

Above
Background
Total Nitrogen
Load Summary

1995-1999






# Freshwater Reach


# Above Background Total Phosphorus Load Summary

1995-1999



## TCAA BMAP Projected Load Reduction 004 Total Nitrogen (255,001 lbs/yr)


#### Current TCAA Project Load Reduction iotal Nitrogen



- Implementation of approved agricultural best management practices on 33,000 acres (100%) of ag crop lands.
- Implementation of 3 regional stormwater treatment facilities.


- Implementation of approved agricultural best management practices on 25,199 acres (76%) of ag crop land.
- Implementation of 2 regional stormwater treatment facilities.

## TCAA BMAP Projected Load Reduction Total Phosphorus (27,458 lbs/yr)



#### Current TCAA Project Load Reduction Total Phosphorus

- Ag in-field BMPs on 25,199 (76%) ac Regional Stormwater Treatment
- Untreated



- Implementation of approved agricultural best management practices on 33,000 acres of ag crop lands (100%).
- Implementation of 4 regional stormwater treatment facilities.
- Implementation of approved agricultural best management practices on 25,199 acres of ag crop lands (76%).
- Implementation of 2 regional stormwater treatment facilities.

## **TCAA Water Management Partnership**


The objective of the TCAA-WMP is to improve health of the lower St. Johns River through on-farm and regional water management projects and practices that reduce the movement of nutrients to the river, improve water conservation, and result in more efficient farm management. The primary concern is the movement of phosphorus off of farm lands into the lower St. Johns River and its tributaries, although nitrogen movement is also a concern.

- TCAA growers (including the North Florida Growers Exchange)
- FDACS (coordinating entity)
- Florida Department of Environmental Protection (DEP)
- SJRWMD

- UF-IFAS
- St. Johns County
- Floridan Resource Conservation and Development Council
- Florida Fruit and Vegetable Association
   Florida
- Farm Bureau
- United States Department of Agriculture Natural Resources Conservation Service (USDA-NRCS)




## **Nutrient Reduction Strategy**




Estimated Reduction Goal 118,107 lbs/yr of TN 16,458 lbs/yr of TP

Implementation of improved irrigation management and nutrient management practices on 18,000 acres of intensive row cropland (i.e., potato and cabbage)

#### Treating the Remaining TN Load (118,107 lbs/yr)



#### Treating the Remaining TP Load (16,458 lbs/yr)





## Funding Status as of June 16, 2014

SJRWMD — \$2.25 million provided \$1.5 million for projects and fertilizer banding \$750,000 for banding only

USDA-NRCS — \$741,000 provided; \$450,000 committed so far

FDACS — \$1.0 million provided

DEP — \$2.3 million provided \$400,000 for monitoring \$1.9 million for projects and fertilizer banding



## Water Management Partnership

2012–2013 Projects and Practices funded to date					
# of Projects	Project Type	Acres	Project Cost	Estimated lbs TP Removed	Estimated lbs TN Removed
5	Subsurface irrigation/drainage (Irridrain)	327	\$612,904	*TBD	*TBD
3	Enhanced seepage (Subsurface drip)	85	\$82,300	165	605
2	Overhead linear irrigation	317	\$451,021	400	1,472
2	Center Pivot overhead irrigation	240	\$605,798	319	1,170
12	Fertilizer banding equipment	8,093	\$813,827	7,121	17,838
2014 New Projects (1st sign-up period)					
3	Enhanced seepage (Subsurface drip)	165	\$261,020	316	1,166
1	Center Pivot overhead irrigation	142	\$168,500	174	640
2	High Tunnel, drip w rainwater harvesting	6	\$358,950	*TBD	*TBD
4	Fertilizer banding equipment	3,150	\$214,362	2,771	6,943

TCAA-WMP projects to date estimated to address ~25% of total needed TN reductions and >50% of TP reductions.





- N and P agricultural nonpoint source loading is primarily associated with storm events.
- Best management practices (BMPs) can reduce nutrient loading from edge of field.
- BMPs should be designed to improve nutrient/plant uptake efficiency; retain nutrients in the field and minimize runoff.





